

## SARVAJANIK EDUCATION SOCIETY

Opp. Chowpatty, Athwalines, M.T.B.College Campus, Surat.

### Quotation Of Civil, PPGI Tile Roof ,Wood work & Colourwork of Daxinabhavan bldg at T.&T.V. Sarvajanik Highschool Nanpura

Name & Address of Contractor :-

Sr.No. **GENERAL CONDITIONS :**

- 1 Above quantities are probable, it may increase or decrease.
- 2 The contractor shall be paid for the actual quantity of work done as measured on site.
- 3 The contractor shall be responsible for the safety & security of all materials brought on site.
- 4 Supply of materials will be your responsibility & SES will not be responsible for shortage of material or delay in supply of material.
- 5 Any type of taxes **INCLUDING GST**, if applicable. SES is not liable to pay any tax.
- 6 All material should be as specified by the Estate Engineer & work should be carried out as per his instructions
- 7 In the event of any dispute decision of the S.E.S.will be final and binding on the contractor.
- 8 SES will not undertake any liability whatsoever for any mishap/accident during the work being carried out.
- 9 Necessary completion certificate for above mentioned **Heritage work** of amount **Rs.45 lakh** to be submitted along with bidding documents.
- 10 The contractor shall take due care not to damage any property of the society while carrying out the work. In the event of any damage to the property, the contractor will solely be held responsible and loss if any will be recovered from the contractor.
- 11 After completion of the work, site should be cleared & cleaned by the contractor & handed over to the Estate Engineer on behalf of SES.
- 12 Electric supply & water will be provided by Client.
- 13 Specifications of abstract items are as per general practice.
- 14 T.D.S. will be deducted as per rules.
- 15 If any extra items which are not provided in abstract, rate will be fixed on basis of quoted rates of similar nature of items in quotation.
- 16 The contractor shall complete the work within **90 DAYS** from the date of work order.
- 17 **10%** of the running bill will be deducted as retention amount and shall be released after six months from the date of final bill.
- 18 Agreed liquidated damages :- Rs.10000 /- per week for delay in work or damage to the property.
- 19 The contractor shall pay **2%** of contract amount as security deposit in case of his quotation being accepted.
- 20 Amount of interim payment :- **10,00,000/-**
- 21 All the pages must be signed & stamped by the contractor.
- 22 Tender last submission **date 10.10.2026** up to 5.0 PM at our S.E.S. Office
- 23 Defect liability period will be consider Six Month ( 180 days /or one monsoon season ) after completion of work.

Place :-

Date :-

STAMP & SIGNATURE OF THE CONTRACTOR

| SARVAJANIK EDUCATION SOCIETY                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                   |        |      |        |
|------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|--------|------|--------|
| Quotation Of Civil,PPGI Tile Roof sheet ,Wood work & Colourwork of Daxinabhavan bldg at T.&T.V. Sarvajanic |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                   |        |      |        |
| Highschool Nanpura                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                   |        |      |        |
| SCHEDULE OF QUANTITIES & RATES                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                   |        |      |        |
| NOTES                                                                                                      | (i) Quantities given below are approximate only and are not binding to the Owner.                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                   |        |      |        |
|                                                                                                            | (ii) For provisional items where the quantities are not mentioned , please submit your rate per unit                                                                                                                                                                                                                                                                                                                                                                                                                                                |                   |        |      |        |
| Sr.No.                                                                                                     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Qty.              | Unit   | Rate | Amount |
| <b>A</b>                                                                                                   | <b>Civil work</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                   |        |      |        |
| 1                                                                                                          | Providing & Laying Smooth / Rough Cement Plaster in C:M 1:4 incl. Dismantling old plaster and charu carting outside the campus , Curing Etc. Complete including scaffolding                                                                                                                                                                                                                                                                                                                                                                         | 2500              | sq.ft. |      |        |
| 2                                                                                                          | Providing & Filling 1" wide cracks with SBR base Polymer ( Chemical) treatment with SBR , recron 3S fiber and Grout incl. removing deteriorated plaster crack etc Completed with required scaffolding                                                                                                                                                                                                                                                                                                                                               | 1250              | Rft.   |      |        |
| 3                                                                                                          | Repairs of old flooring joints with cement & chemical grout etc complete                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 1150              | sq.ft. |      |        |
| 4                                                                                                          | Providing & Laying Double Coat Cement Mala/Tari Plaster in C:M 1:4 incl. Dismantling old plaster and charu carting outside the campus , Curing Etc. Complete including scaffolding.                                                                                                                                                                                                                                                                                                                                                                 | 750               | Rft.   |      |        |
| 5                                                                                                          | P & A SBR Based Polymer Mortar ( Chemicle) treatment upto 25mm in proportion 5Ltr. SBR , 1 pouch (100gms) Recron 3s fiber per 50kg bag of cement including removing deteriorated plaster all loose particles , over all RCC works, stag one side of building and removing by tractor outside the campus,including scaffoldings etc. & Finishing With plaster in 1:4 Mortar with neat slurry in finishing coat at all floors.                                                                                                                        | 500               | Sq.Ft. |      |        |
| 6                                                                                                          | P&L indian style cement based waterproofing wall side vatta in CM 1:4 placing fresh brick bats. And waterproofing chemical ,curing etc.Laid in slope as directed on roof                                                                                                                                                                                                                                                                                                                                                                            | 70                | Rft.   |      |        |
|                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <b>Total Rs.A</b> |        |      |        |
| <b>B</b>                                                                                                   | <b>Roof work</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                   |        |      |        |
| 1                                                                                                          | Labour For Removing manglory tiles including removing batten patti & Removing Vata and manglory tiles staking at ground floor ,one side of campus corner as per instructed by EIC.                                                                                                                                                                                                                                                                                                                                                                  | 6110              | Sq.Ft. |      |        |
| 2                                                                                                          | Providing & fixing 0.5 mm. thick PPGI Tile roof sheet of "Tata Make" Blue scope Brick Red Terracotta colour as approved by the Engineer- in-Charge, having width of 1200 mm. required. as per design and details, with anti-syphoning feature etc., accessories as required, including self drilling screws ,18 gauge plain G I Sheets (3.0 ft width ) in gutter & top plain sheet ridge by as approved, having metal bonded EPDM washer made of stainless steel, as per specifications, etc. as approved by the Engineer-in-Charge, etc. complete. | 6110              | Sq.Ft. |      |        |
| 3                                                                                                          | Providing & fabricating " Appolo" or " Asian" make M.S. square pipes 25x25x2.5mm at 1.0 mtr. c/c For Purline horizontally as per required slope etc complete with including one coat of primer to all m.s. pipe sections & 2 coats of oilpaint with scaffolding work                                                                                                                                                                                                                                                                                | 3580              | kg     |      |        |
| 4                                                                                                          | P & A one coat of primer on plank top etc. including scraping surfaces with sandpaper, required scaffolding,Termite treatment etc. complete.                                                                                                                                                                                                                                                                                                                                                                                                        | 6110              | Sq.Ft. |      |        |
| 5                                                                                                          | P & Fixing of 6" X 3/4" finished size Valsadi sagi seasoned wooden planks ( patiya ) with tung & groove arrangement in line & level,with required scaffolding inside/outside , required hardware materials,including removing old damaged existing Planks ( patiya ) etc. complete.                                                                                                                                                                                                                                                                 | 196               | C Ft.  |      |        |
| 6                                                                                                          | <b>Wooden Stair work</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                   |        |      |        |
| a                                                                                                          | P & Fixing of Valsadi sagi 1.5" thick stair Tapaa Repairing with required scaffolding , hardware materials,including removing old damaged existing sagi Tapaa . ( patiya ) etc. complete.                                                                                                                                                                                                                                                                                                                                                           | 1                 | job    |      |        |
|                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <b>Total Rs.B</b> |        |      |        |

|                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                   |        |  |  |
|------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|--------|--|--|
| <b>C</b>                     | <b>DOORS WINDOWS REPAIRS WORKS</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                   |        |  |  |
| 1                            | Repairs of existing doors & windows frames ,shutters, including replacing damaged teak wood,hardware fittings etc complete with required scaffolding                                                                                                                                                                                                                                                                                                                                           | 1335              | Sq.Ft. |  |  |
| 2                            | P & Making of wooden window chajja with 22 guage GI sheet on top etc coomplete with necessary scaffolding work                                                                                                                                                                                                                                                                                                                                                                                 | 18                | Nos    |  |  |
|                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | <b>Total Rs.C</b> |        |  |  |
| <b>D</b>                     | <b>COLOUR WORK</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                   |        |  |  |
| 1                            | P & A one coat of primer & two coats of <b>Distemper</b> Paint to interior walls & ceilling etc. including full lapi putty, scraping surfaces with sandpaper, required scaffolding etc. complete (Asian make )                                                                                                                                                                                                                                                                                 | 37990             | Sq.Ft. |  |  |
| 2                            | P & A one coat of primer & two coats of <b>Oil paint</b> to doors, windows, walls, ceilling,wooden truss , partitions etc. including full lapi putty, scraping surfaces with sandpaper, required scaffolding etc. complete.(Asian make )                                                                                                                                                                                                                                                       | 21900             | Sq.Ft. |  |  |
| 3                            | P & A one coat of primer & two coats of <b>steel Oil paint</b> to windows's m.s. grills ,passage railings etc. including scraping surfaces with sandpaper, required scaffolding etc. complete.(Asian make )                                                                                                                                                                                                                                                                                    | 1400              | Sq.Ft. |  |  |
| 4                            | P&A One coat of primer and two coats of <b>Weather Shield MAX</b> exterior Paint including cleaning surface, filling cracks, Holes, required scaffolding etc. on outer surface / walls of Building etc. complete (Asian make )                                                                                                                                                                                                                                                                 | 10800             | Sq.Ft. |  |  |
| 5                            | Scraping of old choona of walls & cleaning the wall surface area etc complete with required scaffolding                                                                                                                                                                                                                                                                                                                                                                                        | 5500              | Sq.Ft. |  |  |
|                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | <b>Total Rs.D</b> |        |  |  |
| <b>E</b>                     | <b>ANTI TERMITE TREATNENT</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                   |        |  |  |
|                              | Providing & injecting Imidaclophride 30.5% Sc concentrations by weight for Anti-termite Treatment conforming to IS-6313 (Part II 2022) & creating a chemical barrier (through agency approved by Consultants), under & all around foundation pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall & floor, along the external perimeter of building, expansion joints, surrounding of pipes, water conduits or at places suggested by Engineer In Charge. | 12400             | Sq.Ft. |  |  |
|                              | Note: Performance Guarantee for the treatment for a period of 4 years shall be submitted as per specification                                                                                                                                                                                                                                                                                                                                                                                  |                   |        |  |  |
|                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | <b>Total Rs.E</b> |        |  |  |
| <b>TOTAL AMOUNT (A TO E)</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                   |        |  |  |

Date :-  
Place :-

**STAMP & SIGNATURE OF**  
  
**THE CONTRACTOR**