

SARVAJANIK EDUCATION SOCIETY

Opp. Chowpatty, Athwalines, M.T.B.College Campus, Surat.

Quotation Of Civil, Manglore Tile Roof ,Wood work & Colourwork of Daxinabhavan bldg at T.&T.V. Sarvajanik Highschool Nanpura

Name & Address of Contractor :-

Sr.No. **GENERAL CONDITIONS :**

- 1 Above quantities are probable, it may increase or decrease.
- 2 The contractor shall be paid for the actual quantity of work done as measured on site.
- 3 The contractor shall be responsible for the safty & security of all materials brought on site.
- 4 Supply of materials will be your responsibility & SES will not be responsible for shortage of material or delay in supply of material.
- 5 Any type of taxes **INCLUDING GST**, if applicable. SES is not liable to pay any tax.
- 6 All material should be as specified by the Estate Engineer & work should be carried out as per his instructions
- 7 In the event of any dispute decision of the S.E.S.will be final and binding on the contractor.
- 8 SES will not undertake any liability whatsoever for any mishap/accident during the work being carried out.
- 9 Necessary completion certificate for above mentioned **Heritage work** of amount **Rs.45 lakh** to be submitted along with bidding documents.
- 10 The contractor shall take due care not to damage any property of the society while carrying out the work. In the event of any damage to the property, the contractor will solely be held responceible and loss if any will be recovered from the contractor.
- 11 After completion of the work, site should be cleared & cleaned by the contractor & handed over to the Estate Engineer on behalf of SES.
- 12 Electric supply & water will be provided by Client.
- 13 Specifications of abstract items are as per general practice.
- 14 T.D.S. will be deducted as per rules.
- 15 If any extra items which are not provided in abstract, rate will be fixed on basis of quoted rates of similar nature of items in quotation.
- 16 The contractor shall complete the work within **90 DAYS** from the date of work order.
- 17 **10%** of the running bill will be deducted as retention amount and shall be released after six months from the date of final bill.
- 18 Agreed liquidated damages :- Rs.10000 /- per week for delay in work or damage to the property.
- 19 The contractor shall pay **2%** of contract amount as security deposite incase of his quotation being accepted.
- 20 Amount of interim payment :- **10,00,000/-**
- 21 All the pages must be signed & stamped by the contractor.
- 22 Tender last submission **date 10.10.2026** up to 5.0 PM at our S.E.S. Office
- 23 Defect liability period will be consider Six Month (180 days /or one monsoon season) after completion of work.

Place :-

Date :-

STAMP & SIGNATURE OF THE CONTRACTOR

SARVAJANIK EDUCATION SOCIETY					
Quotation Of Civil,PPGI Tile Roof sheet ,Wood work & Colourwork of Daxinabhavan bldg at T.&T.V. Sarvajani					
Highschool Nanpura					
SCHEDULE OF QUANTITIES & RATES					
NOTES	(i) Quantities given below are approximate only and are not binding to the Owner.				
	(ii) For provisional items where the quantities are not mentioned , please submit your rate per unit				
Sr.No.	Description	Qty.	Unit	Rate	Amount
A	Civil work				
1	Providing & Laying Smooth / Rough Cement Plaster in C:M 1:4 incl. Dismantling old plaster and charu carting outside the campus , Curing Etc. Complete including scaffolding	2500	sq.ft.		
2	Providing & Filling 1" wide cracks with SBR base Polymer (Chemical) treatment with SBR , recron 3S fiber and Grout incl. removing deteriorated plaster crack etc Completed with required scaffolding	1250	Rft.		
3	Repairs of old flooring joints with cement & chemical grout etc complete	1150	sq.ft.		
4	Providing & Laying Double Coat Cement Mala/Tari Plaster in C:M 1:4 incl. Dismantling old plaster and charu carting outside the campus , Curing Etc. Complete including scaffolding.	750	Rft.		
5	P & A SBR Based Polymer Mortar (Chemicle) treatment upto 25mm in proportion 5Ltr. SBR , 1 pouch (100gms) Recron 3s fiber per 50kg bag of cement including removing deteriorated plaster all loose particles , over all RCC works, stag one side of building and removing by tractor outside the campus,including scaffoldings etc. & Finishing With plaster in 1:4 Mortar with neat slurry in finishing coat at all floors.	500	Sq.Ft.		
6	P&L indian style cement based waterproofing wall side vatta in CM 1:4 placing fresh brick bats. And waterproofing chemical ,curing etc.Laid in slope as directed on roof	70	Rft.		
		Total Rs.A			
B	Roof work				
1	Labour For Removing manglory tiles including removing batten patti & Removing Vata and manglory tiles staking at ground floor ,one side of campus corner as per instructed by EIC.	6110	Sq.Ft.		
2	Fixing of old manglore tiles in line & level etc complete with new sagi 2" X1" bidding patti ,hardware fittings & mobhiya on top	2000	Sq.Ft.		
3	P & Fixing of New manglore tiles in line & level etc complete with new sagi 2" X1" bidding patti ,hardware fittings & mobhiya on top	4110	Sq.Ft.		
4	P & A one coat of primer on plank top etc. including scraping surfaces with sandpaper, required scaffolding,Termite treatment etc. complete.	6110	Sq.Ft.		
5	P & Fixing of 6" X 3/4" finished size Valsadi sagi seasoned wooden planks (patiya) with tung & groove arrangement in line & level,with required scaffolding inside/outside , required hardware materials,including removing old damaged existing Planks (patiya) etc. complete.	196	C Ft.		
6	Wooden Stair work				
a	P & Fixing of Valsadi sagi 1.5" thick stair Tapaa Repairing with required scaffolding , hardware materials,including removing old damaged existing sagi Tapaa . (patiya) etc. complete.	1	job		
		Total Rs.B			
C	DOORS WINDOWS REPAIRS WORKS				
1	Repairs of existing doors & windows frames ,shutters, including replacing damaged teak wood,hardware fittings etc complete with required scaffolding	1335	Sq.Ft.		
2	P & Making of wooden window chajja with 22 guage GI sheet on top etc coomplete with necessary scaffolding work	18	Nos		
		Total Rs.C			

D	COLOUR WORK				
1	P & A one coat of primer & two coats of Distemper Paint to interior walls & ceiling etc. including full lapi putty, scraping surfaces with sandpaper, required scaffolding etc. complete (Asian make)	37990	Sq.Ft.		
2	P & A one coat of primer & two coats of Oil paint to doors, windows, walls, ceiling, wooden truss , partitions etc. including full lapi putty, scraping surfaces with sandpaper, required scaffolding etc. complete.(Asian make)	21900	Sq.Ft.		
3	P & A one coat of primer & two coats of steel Oil paint to windows's m.s. grills ,passage railings etc. including scraping surfaces with sandpaper, required scaffolding etc. complete.(Asian make)	1400	Sq.Ft.		
4	P&A One coat of primer and two coats of Weather Shield MAX exterior Paint including cleaning surface, filling cracks, Holes, required scaffolding etc. on outer surface / walls of Building etc. complete (Asian make)	10800	Sq.Ft.		
5	Scraping of old choona of walls & cleaning the wall surface area etc complete with required scaffolding	5500	Sq.Ft.		
		Total Rs.D			
E	ANTI TERMITE TREATMENT				
	Providing & injecting Imidaclophride 30.5% Sc concentrations by weight for Anti-termite Treatment conforming to IS-6313 (Part II 2022) & creating a chemical barrier (through agency approved by Consultants), under & all around foundation pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall & floor, along the external perimeter of building, expansion joints, surrounding of pipes, water conduits or at places suggested by Engineer In Charge.	12400	Sq.Ft.		
	Note: Performance Guarantee for the treatment for a period of 4 years shall be submitted as per specification				
		Total Rs.E			
		TOTAL AMOUNT (A TO E)			

Date :-
Place :-

STAMP & SIGNATURE OF

THE CONTRACTOR